IN THE SPECIFICATION:

Replace the paragraph beginning at page 35, line 4, with the following rewritten paragraph:

--The temperature in a room for assembling the die was set to 22 $^{\circ}C$, the water of 22 $^{\circ}C$ passed through the passage provided inside each of the two blocks 102, 105 for two hours. Thus the temperature of the blocks 102, 105 was adjusted to 22 $^{\circ}C$. The overbite length LO1 was measured with the optical microscope 123 and adjusted to be 50 μm. The holding mechanism 112, the fixer 111, the bolts 106 and the thickness gage 86 were removed after adjustment of the overbite length LO1.--